ADDENDUM TO SOLICITATION/OFFER AND AWARD

1. ADDENDUM	2. EFFECTIVE DATE	3. SOLICITATION NUMBER	4. SOLICITATION DESCRIPTION
1	February 23,2022	ITB 22-01	Signage Campus Wide

5. ISSUED BY:

LAKE-SUMTER STATE COLLEGE
TAMMY SPENCER, DIRECTOR OF PURCHASING
9501 U.S. HWY 441
WILLIAMS-JOHNSON BLDG./ROOM 133
LEESBURG, FLORIDA   34788-3950

TELEPHONE: (352) 365-3502   FAX:

7. TYPE OF ACTION REQUESTED

Check one:

☐ A. THE CHANGE ORDER IS ISSUED TO INCREASE/DECREASE FUNDING AMOUNT AS SET FORTH IN ITEM 8 BELOW:

☐ B. THE ABOVE NUMBERED SOLICITATION IS MODIFIED TO REFLECT THE ADMINISTRATIVE CHANGES SET FORTH IN ITEM 8 BELOW:

☒ C. OTHER (Set forth in Item 8 below)

IMPORTANT: CONTRACTOR ☒ IS NOT REQUIRED TO SIGN THIS DOCUMENT AND RETURN ___1___ ORIGINAL SIGNED COPY (IES) TO THE ISSUING OFFICE.

☐ IS REQUIRED TO SIGN THIS DOCUMENT AND RETURN ___1___ ORIGINAL SIGNED COPY (IES) TO THE ISSUING OFFICE.

8. DESCRIPTION OF ADDENDUM:

This addendum serves as notice that the schedule of events listed on page 17 has been changed in regards to last day for questions is Friday, February 25,2022, Bid DUE DATE is now Friday, March 04,2022 @ 2:00 PM, and Public Bid Opening is now Friday, March 04,2022 @ 2:30 PM. Furthermore, please see the clarification of scope on next page that LSSC would like to provide to all potential bidders.

- All sign designs are double sided with EMC video displays located on both sides.
- LSSC has provided the design concepts and descriptions listed in Section E of the ITB 22-01 document. No sign engineering or structural engineering documents have been created. The bidder is responsible for providing these engineering documents, sufficient for permit approval, as part of this project. All engineered specifications must meet or exceed current Florida Building Code. College requires that each sign should be wind rated for 160mph. Engineering documents should be signed by an engineer licensed by Florida Board of Professional Engineers.
- Bidder should utilize LED lighting and make all other efforts to create an energy efficient sign.
- LSSC intends to install the signs at the following locations, subject to permitting approval.
  - Sign One (Sumter Center): At the intersection of U.S. 301 and County Road 526E in Sumterville, FL in the median. This sign will replace the College's existing sign at this location. Existing footings should be removed completely or cut down to below grade.
  - Sign Two (South Lake Campus): On the College's campus along N. Hancock Rd. between the two southbound entrances onto College property from southbound N. Hancock Rd. at the site of the existing monument sign. Sign Two should utilize footing from existing sign.
  - Sign Three (Leesburg Campus): At the northeast corner of the entrance to the College's campus on U.S. Highway 441 and Crofton Dr. located on/near the College's property line and adjacent FDOT right-of-way, subject to FDOT approval. No existing signage at this location.
- Scope of work for this project does not include the stone work or landscaping.
  - Stone work around Signs One and Three is planned to be 48 inches tall.
  - For this project, Signs One and Three should be painted aluminum to the ground. Stone work and landscaping will be added by College at a later date.
  - Stone work around Sign Two is planned to be 24 inches tall. Sign Two should be aluminum to the ground but bottom 24 inches should be covered in hardie board. Stone work and landscaping will be added by College at a later date.
- Electronic Message Centers
  - Each sign's video display board should be able to individually scheduled with location specific content.
  - The College's Information Technology team will provide assistance with adding video displays to the College's secure network. In compliance with the College's IT security policies, individual displays will not have direct access to the internet via LSSC's network.
  - In lieu of wired networking connections to video display, bidder can opt to provide cellular connections. However, College prefers no recurring subscription fees associated with cellular connections.
  - Any additional or recurring costs for networking should be listed as separate line items.

9. AUTHORIZED SIGNATURES REQUIRED

TAMMY SPENCER   Director of Purchasing
_____
NAME (PRINT)   TITLE

_____
SIGNATURE   DATE SIGNED